

**REPLIES TO QUERIES**

<b>S.no</b>	<b>Items</b>	<b>QUERRIES</b>	<b>Replies</b>
1	Item No 1	There is no star rating designated for Tower ACs of 4 TR capacity by BEE.	This is mentioned in the technical specifications & BEE Star Rating is not applicable for Tower Acs of 4TR capacity.
2	Item No 1	The OEMs do not warranty Compressors for 5 Years.	Warranty to be as per terms of OEM . The same has to be mentioned separately by the vendors for quoted units.
3	Item No 1	The Specification sheet attached do not comply completely with the specifications of the suggested Makes ( i.e. Daikin/Panasonic/Carrier/Voltas )	These are the Minimum guiding specifications as required to be complied with by the vendors and may not exactly match the specifications of the suggested makes. The minimum COP value must be adhered to by the vendor.
4	Item No 2	This Item is not completely defined. Do you require "made to specifications Power Distribution & Control Panel" with one incomer ( MCCB ) and Buss bars (Cu/Al), four outgoing tripping devices ( MCB TPN ) two Timers, four Power-Contactors, indicators, V-Meter, Amp. Meters etc.?	Details of Revised Item No 2 of the BOQ is Attached
5	Item No 3	The inter-connecting electric conductors are specified differently by OEMs.	This shall be as per OEM and rate as per specification of the the said item be quoted for..
6		The last date for the submission of Tender	11th June 2018 (Monday ) at 3.00 PM

S.No	Particulars	Qty.	Unit	Rate	Total
2	Design, manufacture, supply, installation, testing and commissioning of the duty sharing arrangement MV panel with timer - front operated, cubicle construction, Floor/Wall mounted type, fabricated out of 2 mm thick CRCA Sheet, Compartmentalized with hinged lockable doors, dust and vermin proof, Powder coated of approved shade after 7 tank treatment, Cable alley, inter-connections, having Switch gear and accessories mounting, internal wiring, earth terminals, Top/ Bottom cable entry, numberings etc. suitable for operation of 415 volts, 3 phase, 4 wire, 50 Hz, AC Supply with enclosure protection class IP 54, with auto manual switch complete as required and as specified with the following:				
	1 No. 125 Amps MCCB incoming.				
	1 Set of phase indicating lights (RYB) with protection MCB.				
	4 Set of ON/ OFF indicating lamp.				
	125 Amp TPN busbars of aluminium alloy.				
	4 Nos. 32-40 Amps Four Pole Miniature Circuit Breaker (10KA). outgoing along with Contactors				
	2 Nos Timers	1	No		